

EROSION LOG (CURLEX OR EQUAL)

WOOD STAKE,
SEE SECTION 3

2'-0" O.C.

STAKE TO BE PLACED AT
TOE OF SLOPE, BOTH SIDES

1 SECTION: EROSION LOGS (NO BLANKET)
NO SCALE

- NOTES:
- 12" DIA. EROSION LOGS
 - SPACING ACCORDING TO MANUFACTURER RECOMMENDATIONS

EROSION LOG (CURLEX OR EQUAL)

WOOD STAKE,
SEE SECTION 3

2'-0"

2'-0" O.C.

EROSION CONTROL BLANKET
INSTALL PER MANUFACTURER

2 SECTION: EROSION LOGS (WITH BLANKET)
NO SCALE

- NOTES:
- 12" DIA. EROSION LOGS
 - SPACING ACCORDING TO MANUFACTURER RECOMMENDATIONS

EROSION LOGS

WOOD STAKE

WOOD STAKE PER
MANUFACTURER'S
RECOMMENDATION

CHANNEL
BOTTOM

45° TO 60°

16" MINIMUM

3 SECTION: STAKE DETAILS (NO TRENCH)
NO SCALE

WOOD OR STEEL POSTS
SPACED 6" O.C. MAX.

FILTER FABRIC MATERIAL

FILTER FABRIC MATERIAL SECURELY
FASTENED TO THE POSTS

APPROX. 12" OF FILTER FABRIC MATERIAL
MUST EXTEND INTO A TRENCH AND BE
ANCHORED WITH COMPACTED BACKFILL
MATERIAL

RUNOFF

APPROX. 6" BY 6" TRENCH

4 DETAIL: SILT FENCE
NO SCALE

NOTES:

- WORK SHALL BE PERFORMED IN ACCORDANCE TO STORM WATER POLLUTION PREVENTION PLAN (SWPPP).
- SILT FENCE AND EROSION CONTROL FEATURES MUST BE INSTALLED PRIOR TO SOIL DISTURBANCE.
- SILT FENCE OR OTHER APPROVED BMP MUST BE PLACED TO INTERCEPT RUNOFF FROM TURBINE AREAS, COLLECTION SYSTEM, TRANSMISSION LINES, SUBSTATIONS AND DISTURBED AREAS THAT ARE LOCATED WITHIN 200 FEET OF ANY SURFACE WATER.
- EROSION LOGS OR CERTIFIED WEED FREE STRAW BALES MAY BE USED AS ALTERNATIVES TO SILT FENCE.
- REVEGETATION AND RESTORATION ACTIVITIES MUST BE CONDUCTED IN ACCORDANCE WITH THE SITE SPECIFIC RESTORATION AND WEED MANAGEMENT PLAN (ATTACHMENT H OF SWPPP).
- DITCH PROTECTION: SILT FENCE, CHECK DAMS OR EROSION LOGS SHALL BE IMPLEMENTED ALONG ROADS AND ADJACENT TO SURFACE WATER AND DRY WASH CROSSINGS AS NECESSARY TO PREVENT EROSION IN DITCHES AND TRANSFER OF SEDIMENT.
- REMOVE SOIL TRACKED ONTO IMPERVIOUS ROADS DAILY.
- FOR PIPES GREATER THAN OR EQUAL TO 30", USE 1.5'.
- THE FABRIC SHOULD COVER THE AREA OF THE RIPRAP AND EXTEND UNDER THE CULVERT APRON 3 FEET.

SEE NOTE 8

RIPRAP

GEOTEXTILE FABRIC
SEE NOTE 9

SECTION B-B

B

PLAN

SEE NOTE 8

GEOTEXTILE FABRIC
SEE NOTE 9


SECTION A-A

RIPRAP QUANTITIES AT
CULVERT OUTLETS

DIA. OF PIPE (INCHES)	L (FEET)	RIPRAP (CU. YD.)
18	10	9.4
24	12	13.0
30	14	17.1
36	16	21.8
42	18	27.0

5 DETAIL: RIPRAP
NO SCALE

A	KKB	CAD	JXB	07/15/11	60 PERCENT SUBMITTAL
B	CAD	CAD	JXB	09/02/11	90 PERCENT SUBMITTAL
C	CAD	CAD	JXB	09/30/11	ISSUED FOR CONSTRUCTION
1	NJG			1/3/13	CONSTRUCTION REVISIONS, NO CHANGES
NO.	BY	CHK	APP.	DATE	REVISION DESCRIPTION



CLIENT	07/15/11	09/02/11					
BID							
CONSTRUCTION							
PERMITTING							
RECORD							
RELEASED TO/FOR	A	B	C	O	1	2	3



Project Office:
BARR ENGINEERING CO.
4700 WEST 77TH STREET
MINNEAPOLIS, MN.
55435-4803
Ph: 1-800-632-2277
Fax: (952) 832-2601
www.barr.com

Scale	AS SHOWN
Date	07/05/11
Drawn	KKB
Checked	JXB
Designed	CAD
Approved	JXB



BISON 3 WIND PROJECT
MORTON & OLIVER COUNTIES, NORTH DAKOTA
EROSION CONTROL
SECTIONS AND DETAILS

BARR PROJECT No.	34/30-1006
CLIENT PROJECT No.	
DWG. No.	C-05
REV. No.	1